



DEDICATION TO QUALITY MANUFACTURING AND INNOVATIVE DESIGN

DEVELOPMENT MONORAIL SYSTEM

The Development Monorail system has proven to assist in the increase of advance rates within the main-gate development unit, in a manner which greatly reduces the risk of personal injury and equipment wear and damage.

Ventilation improvements have been also recognised. As opposed to handling the cumbersome vent tubes and ancillary services (including cables, hoses, pumps, firefighting, stone dusting, fans, gate end boxes and similar), equipment handling is limited to a lightweight monorail beam.

The autonomous Drive system negates the need for diesel equipment. Miner flitting times have been reduced significantly, constantly achieved within 30 minutes. Face services are no longer handled during this process.

Fan and gate end boxes may be trammed inbye within 30 minutes, without the aid of diesel equipment. No cable and hose work is required. The outbye services system extends from the transformer cut-through, incorporating all hoses and cables.



www.macmfg.com.au

Head Office:

6 Immarna Road Rathmines NSW 2283

PH: +61 (0)2 4970 1100 Fax: +61 (0)2 4975 3486

Illawarra Office:

45 Montague Street Nth Wollongong NSW 2500

PH: +61 (0)2 4226 6308 Fax: +61 (0)2 4226 3532

Mackay Office:

PO Box 812 Mackay QLD 4740

Ph: +61 (0)7 4951 1995 Fax: +61 (0)2 4975 3486

A.B.N 12 001 813 387